

RISK ASSESSMENT AND METHOD STATEMENT (RAMS)

Project Name:	Sample Construction Project	Document No:	RAMS-2024-001
Client:	ABC Construction Ltd	Revision:	1.0
Site Address:	123 Main Street, Dublin	Date:	26/01/2026
Task Description:	General Site Works - Groundworks and Foundations		

1. SCOPE OF WORKS

This RAMS covers the following activities: • Site setup and establishment • Excavation works for foundations • Concrete pouring and curing • General construction activities • Material handling and storage

2. HAZARD IDENTIFICATION AND RISK ASSESSMENT

Risk Rating: L = Low (1-4), M = Medium (5-9), H = High (10-16), VH = Very High (17-25)

Likelihood: 1=Rare, 2=Unlikely, 3=Possible, 4=Likely, 5=Almost Certain

Severity: 1=Negligible, 2=Minor, 3=Moderate, 4=Major, 5=Catastrophic

Hazard	Who at Risk	L	S	Risk	Control Measures	L	S	Residual
Working at Height	Operatives	4	4	H	Edge protection, harnesses, trained personnel, scaffolding inspections	2	4	M
Excavation Collapse	Operatives	3	5	H	Shoring/battering, daily inspections, exclusion zones, competent person supervision	2	4	M
Moving Plant/Vehicles	All personnel	4	4	H	Banksmen, pedestrian routes, high-vis PPE, vehicle segregation	2	3	M
Manual Handling	Operatives	4	3	M	Mechanical aids, team lifting, training, weight limits	2	2	L
Noise Exposure	All personnel	4	3	M	Hearing protection, equipment maintenance, exposure monitoring	2	2	L
Slips, Trips, Falls	All personnel	4	3	M	Good housekeeping, designated walkways, appropriate footwear	2	2	L
Electrical Hazards	Operatives	3	5	H	CAT scanner, permit to dig, isolation procedures, competent persons	1	4	M
Dust/Silica	Operatives	4	4	H	Wet cutting, LEV, RPE, health surveillance	2	3	M

3. METHOD STATEMENT

Step	Activity	Responsible Person	Key Controls
1	Site Induction - All personnel to receive site-specific induction	Site Manager	Emergency procedures, site hazards and hazards
2	Area Preparation - Mark out work area, install barriers and signage	Signaller	Identify underground utilities, CAT scanner
3	Excavation - Excavate to required depth using appropriate equipment	Excavation Operator	Permit to dig, daily inspections, access/egress
4	Foundation Works - Install formwork, place reinforcement, pour concrete, allow curing	Formman	Delivery tickets, cube tests
5	Backfill and Reinstatement - Backfill in layers, compact as appropriate, reinstate surface	Supervisor	Compaction tests
6	Site Clearance - Remove all plant and materials, clean work area	Site Manager	Final inspection checklist

4. PERSONAL PROTECTIVE EQUIPMENT (PPE)

The following PPE is mandatory for all personnel on site: • Hard hat (EN 397) • High visibility vest/jacket (EN ISO 20471 Class 2 minimum) • Safety footwear with steel toe and midsole protection (EN ISO 20345 S3) • Safety glasses (EN 166) - when required • Hearing protection (EN 352) - in designated areas • Gloves appropriate to task (EN 388) • RPE (EN 149 FFP3) - when working with silica/dust

5. EMERGENCY PROCEDURES

Emergency Contact Numbers:

- Emergency Services: 999 / 112
- Site Manager: John Smith - 087 123 4567
- H&S; Manager: Jane Doe - 087 234 5678
- Nearest Hospital: St. James's Hospital - 01 410 3000

In case of emergency:

1. Raise the alarm and make the area safe
2. Contact emergency services if required (999/112)
3. Administer first aid if trained and safe to do so
4. Report to Site Manager immediately
5. Do not move injured persons unless in immediate danger
6. Preserve the scene for investigation

6. DOCUMENT APPROVAL AND SIGN-OFF

Role	Name	Signature	Date
Prepared By:			
Reviewed By:			
Approved By:			

7. TOOLBOX TALK / BRIEFING RECORD

All personnel must sign below to confirm they have read, understood, and will comply with this RAMS:

Name (Print)	Company	Signature	Date

[illegible]